

DES Engine

Reference Manual

A discrete-event simulation engine in the spirit of Arena's Basic Process template, written from the simulation theory table up. This manual lists every public type and member, says what each one is for, and traces what actually calls what when a model runs.

The signatures here are **extracted from the headers** when the manual is built, so they cannot drift from the code. Only the prose is written by hand.

v15.2 -- a gate you can wait for - 1383 checks - 120 types

Contents

1. Reading This Manual

What is in here, how it was produced, and the shape of the engine as a whole.

2. Foundations

Time, entities, events, and the accumulators every reported number comes from.

3. Queues and Resources

Waiting lines, the disciplines that order them, and the servers they wait for.

4. Randomness

One primitive, twelve distributions, and the tests that show a generator is sound.

5. The Expression Layer

How a model's conditions, values and durations became text rather than compiled code.

6. The Document Layer

How a model stopped being a program and became a set of spreadsheets.

7. Runtime Control

How a run stopped being something you wait for and became something you drive.

8. The Terminal UI

How the spreadsheets got a screen, and how a terminal interface is tested.

9. Editing a Model

The text editor, the palette, and why the file itself is what gets edited.

10. The Flowchart

The blocks entities move through, and the narrow window each one gets on the engine.

11. The Model

What is simulated, kept separate from the machinery that simulates it.

12. Running a Simulation

The engine, the stopping rules, and the trace that makes a run checkable by hand.

13. Experiments

Why one run is one sample, and what to do about it.

14. Call Flows

What calls what, in order, when a model is built and run.

15. Free Functions

The factories and helpers that are not members of anything.

Chapter 1

Reading This Manual

What is in here, how it was produced, and the shape of the engine as a whole.

This manual documents every public type and member of the engine. It is generated: **the signatures are read out of include/*.hpp when the PDF is built**, so they cannot drift from the code. Only the prose is written by hand. If a member appears here it exists; if one is deleted from the code it disappears from the manual on the next build.

Conventions

Shown	Means
class	Has invariants to protect; members default to private.
struct	A bag of values, all public.
enum class	A closed set of named alternatives.
inherits	Base classes, so the polymorphism is visible.
I-prefix	An interface: pure virtual, implemented elsewhere.

Members are listed in header order rather than alphabetically, because header order is how the author grouped them and that grouping carries meaning.

The engine in layers

Experiments Experiment - Summary - replications, intervals
Engine SimulationSystem - Clock - FutureEventList - Trace
Model Model - INode - Station - Resource
Expressions Parser - IExpression - EvalContext - VariableStore
Foundations Entity - Statistics - RandomStream - Diagnostic

Each layer uses the ones below it. The expression layer sits at the bottom rather than beside the model, because it must not depend on Model: it declares IModelState and the engine implements it.

The one rule worth knowing first

Inside the run loop the integrals for the interval that just ended are closed **before** the clock moves, and the clock moves **before** any state changes. Swap any two of those and every time-weighted average goes quietly wrong, with no error anywhere. Chapter 13 shows the order explicitly.

Chapter 2

Foundations

Time, entities, events, and the accumulators every reported number comes from.

EventType

enum class · Common.hpp

What kind of thing an event notice represents. The engine dispatches on this in the run loop.

Values Arrival, StartService, Departure, EndSimulation, WarmUpEnd, Observe, Renege

QueueDiscipline

enum class · Common.hpp

The service order a queue uses. Selects which IQueueRule a station is built with.

Values FIFO, LIFO, Priority, Random, SPT, EDD

ResourceState

enum class · Common.hpp

Whether a resource is idle, partly busy, or fully seized.

Values Idle, Busy

Clock

class · Clock.hpp

Simulation time, and the invariant that it never goes backwards. `advanceTo()` is the only door, which is why the class exists rather than a bare double.

SimTime now() const
The current simulation time.

void advanceTo(SimTime t)
Moves time forward. Refuses to go backwards -- the invariant the class exists to protect.

void reset()
Back to the `t=0` condition. Configuration survives; run state does not.

Entity

class · Entity.hpp

The thing that flows through the model: a customer, a part, a patient. Carries an id, a creation time, a type name, and an open-ended bag of numeric attributes.

EntityId id() const
The unique id assigned at creation.

SimTime creationTime() const
When this entity entered the system. Copies inherit the original's, because they are the same work.

void setAttribute(const std::string& name, double value)
Inserts or overwrites an attribute.

double attribute(const std::string& name) const
Reads a numeric attribute. Returns 0.0 when absent, which is why callers that care check `hasAttribute()` first.

bool hasAttribute(const std::string& name) const
Whether the attribute has ever been set on this entity.

void copyAttributesFrom(const Entity& other)
Copies every attribute from another entity. Used when duplicating.

void addMember(Entity* e)
Adds an entity to this one's batch. A batch representative carries its members until a Separate splits them out.

const std::vector<Entity*> members() const
The entities this batch representative is carrying.

bool isBatch() const

Whether this entity is carrying members.

void clearMembers()

Drops the carried members, after a Separate has released them.

void setCreationTime(SimTime t)

Overrides the creation time. Used when a copy must inherit the original's, because it is the same work.

const std::string& type() const

The entity's type name, which per-type reporting is keyed on.

void setType(std::string t)

Changes the type name. Prefer `NodeContext::setEntityType`, which also moves the live per-type count.

EventNotice

class · EventNotice.hpp

One scheduled future occurrence: a time, a kind, and optionally the entity and block it concerns. Ordered by time, with a sequence number breaking ties so equal-time events keep their scheduling order.

EventType type() const
The type.

SimTime time() const
The time.

Entity* entity() const
The entity.

Inode* node() const
The node.

uint64_t sequenceNumber() const
A monotonically increasing stamp used only for tie-breaking.

bool operator>(const EventNotice& other) const
Orders notices for the heap: earlier times first, with the sequence number breaking ties so equal-time events keep scheduling order.

FutureEventList

class · FutureEventList.hpp

The pending-event set, kept as a binary heap ordered by time. `popImminent()` is the beating heart of the run loop. It cannot remove an arbitrary element, which is why reneging uses lazy cancellation instead.

bool isEmpty() const
Whether anything is still scheduled. The run loop stops when this is true.

std::size_t size() const
How many events are pending.

void clear()
Discards every pending event. Part of resetting between replications.

void schedule(EventNotice e)
Inserts a notice into the heap.

EventNotice popImminent()
Removes and returns the earliest notice. The centre of the run loop.

SimTime nextEventTime() const
When the next event is due, without removing it.

Activity

class · Activity.hpp

A span whose duration is known when it starts -- a service time drawn at seize. `endTime()` is derived, never stored, so the two cannot disagree.

Activity(std::string name, SimTime start, SimTime duration)
 Constructor.

const std::string& name() const
 The name this object was constructed with.

SimTime startTime() const
 The start time.

SimTime duration() const
 The duration.

SimTime endTime() const
 Start plus duration, derived rather than stored so the two cannot disagree.

Delay

class · Delay.hpp

A span whose duration is decided later, by the system rather than by a draw -- how long an entity waited for a server to free up.

explicit Delay(SimTime start)
 Constructor.

SimTime startTime() const
 The start time.

bool hasEnded() const
 Whether this delay has been closed.

void end(SimTime t)
 Closes the delay at the given time.

SimTime duration() const
 The duration.

SystemState

class · SystemState.hpp

A snapshot of the whole system: number in system, number queued, server status. Summed across stations rather than owned by any one of them.

int numberInSystem() const
 The number in system.

int numberInQueue() const
 The number in queue.

ResourceState serverStatus() const
 Whether servers are idle, busy or fully seized.

void setNumberInSystem(int count)
 Sets the number in system.

void setNumberInQueue(int count)
 Sets the number in queue.

void setServerStatus(ResourceState status)
 Sets the server status.

void reset()
 Back to the t=0 condition. Configuration survives; run state does not.

Statistics

class · Statistics.hpp

The accumulators behind every reported average. Holds counts, totals and two time integrals, and knows the difference between a tally average and a time-weighted one.

Statistics(std::string labelA, std::string labelB)
 Constructor.

int numberArrived() const
 How many arrivals were counted.

int numberServed() const
 How many departures were counted.

SimTime totalWaitingTime() const
 The total waiting time.

SimTime totalTimeInSystem() const
 The total time in system.

SimTime maxWaitingTime() const
 The max waiting time.

SimTime areaA() const
 The raw first integral. Divide by measured time for the average.

SimTime areaB() const
 The raw second integral. Divide by measured time for the average.

SimTime lastUpdateTime() const
 When the integrals were last closed.

const std::string& labelA() const
 The label a.

const std::string& labelB() const
 The label b.

void recordArrival(SimTime t)
 Counts an arrival.

void recordDeparture(SimTime t, SimTime waitTime, SimTime timeInSystem)
 Counts a departure and accumulates its waiting time and time in system.

void updateTimeIntegrals(SimTime now, int valueA, int valueB)
 Closes the interval that just ENDED, so it must be called before the clock moves and before any state changes, with the OLD values.

void reset()
 Back to the t=0 condition. Configuration survives; run state does not.

void restartAt(SimTime now)
 Throws away everything collected and starts accumulating from now. Warm-up removal in one line.

double averageWaitingTime() const
 The average waiting time.

double averageTimeInSystem() const
 The average time in system.

double timeAverageA(SimTime elapsed) const
 The first time-weighted average over the measured interval. The caller supplies the elapsed time so that warm-up handling is visible.

double timeAverageB(SimTime elapsed) const
 The second time-weighted average over the measured interval.

double utilisation(SimTime elapsed, int capacity) const
 Busy server-time divided by capacity times elapsed time.

ModelError

class · ModelError.hpp · inherits public std::runtime_error

Thrown when a model is wired wrongly -- a programmer's mistake, where stopping is the right response. Contrast Diagnostic, which is how a user's mistake is reported.

explicit ModelError(const std::string& what) :
std::runtime_error(what)
 Constructor.

Chapter 3

Queues and Resources

Waiting lines, the disciplines that order them, and the servers they wait for.

A queue holds entities; a rule decides which one leaves next; a resource is the pool of servers they are waiting for. Resources are owned by the **Model** rather than by a block, which is what makes one operator shared across three machines expressible at all.

EntityQueue

class · EntityQueue.hpp

A waiting line: a deque of entities plus a pluggable rule that chooses which one leaves next. Tracks its own maximum observed length.

```
EntityQueue(const std::string& name, QueueDiscipline
discipline)
    Constructor.

EntityQueue(const std::string& name,
std::unique_ptr<IQueueRule> rule)
    Constructor.

const std::string& name() const
    The name this object was constructed with.

std::string ruleName() const
    The discipline's name, for reports.

std::size_t length() const
    The length.

bool isEmpty() const
    Whether anything is waiting here.

std::size_t maxLengthObserved() const
    The longest this queue has ever been.

const std::deque<Entity*>& contents() const
    The waiting entities, in arrival order, whichever discipline is in use.

void setRandomStream(RandomStream* rng)
    Supplies the stream the Random discipline draws from.

void reset()
    Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics()
    Discards measurements collected so far and starts again from now,
without touching what is held. This is warm-up removal at block level.

void push(Entity* e)
    Adds an entity to the back of the line.

Entity* pop()
    Removes and returns the entity the discipline selects.

bool remove(Entity* e)
    Removes a specific entity if it is still waiting, and reports whether it
was. How reneging works.
```

IQueueRule

class · QueueRule.hpp

The interface a queue discipline implements. One method: given the waiting entities, which index is served next.

```
virtual std::string name() const = 0
    The name this object was constructed with.
```

FifoRule

class · QueueRule.hpp · inherits public IQueueRule

First in, first out. Always index 0.

```
std::size_t selectIndex(const std::deque<Entity*>&,
RandomStream&) const override
    Which waiting entity is served next, as an index into the queue.

std::string name() const override
    The name this object was constructed with.
```

LifoRule

class · QueueRule.hpp · inherits public IQueueRule

Last in, first out. Always the final index.

```
std::size_t selectIndex(const std::deque<Entity*>&,
RandomStream&) const override
    Which waiting entity is served next, as an index into the queue.

std::string name() const override
    The name this object was constructed with.
```

HighestAttributeRule

class · QueueRule.hpp · inherits public IQueueRule

Serves whichever waiting entity has the largest value of a named attribute -- the Priority discipline. Ties resolve to the earliest arrival, deliberately.

```
explicit HighestAttributeRule(std::string attribute)
    Constructor.

std::size_t selectIndex(const std::deque<Entity*>&,
RandomStream&) const override
    Which waiting entity is served next, as an index into the queue.

std::string name() const override
    The name this object was constructed with.
```

LowestAttributeRule

class · QueueRule.hpp · inherits public IQueueRule

Serves the smallest value of a named attribute -- shortest processing time, or earliest due date.

```
explicit LowestAttributeRule(std::string attribute)
    Constructor.

std::size_t selectIndex(const std::deque<Entity*>&,
RandomStream&) const override
    Which waiting entity is served next, as an index into the queue.

std::string name() const override
    The name this object was constructed with.
```

RandomRule

class · QueueRule.hpp · inherits public IQueueRule

Picks a waiting entity uniformly at random, drawing from the queue's random stream.

```
std::size_t selectIndex(const std::deque<Entity*>&,
RandomStream&) const override
    Which waiting entity is served next, as an index into the queue.

std::string name() const override
    The name this object was constructed with.
```

IResourceUser

class · Resource.hpp

The interface a block implements to compete for a shared resource: can it start something, and how long has its longest-waiting entity been waiting.

```
virtual bool hasWaiting() const = 0
    Whether waiting.

virtual SimTime headOfLineSince() const = 0
    When this user's longest-waiting entity started waiting. The resource
compares this across every block sharing it, so the longest waiter
anywhere is served next.

virtual void startFromQueue(NodeContext& ctx) = 0
```

Asks this user to start serving its next queued entity, if it can. Returning without seizing tells the resource to stop offering.

Resource

class · Resource.hpp

A pool of interchangeable servers with a capacity. Owned by the Model, not by a block, which is what lets several blocks share one operator. When a unit frees, the resource offers it to whichever user has waited longest.

Resource(std::string name, int capacity)

Constructor.

const std::string& name() const

The name this object was constructed with.

int capacity() const

How many units this resource has.

int unitsBusy() const

The units busy.

int unitsAvailable() const

Capacity minus units busy, derived rather than stored.

bool isAvailable() const

Whether at least one unit is free.

ResourceState state() const

The state.

void reset()

Back to the t=0 condition. Configuration survives; run state does not.

void addUser(IResourceUser* user)

Registers a block as a competitor for this resource.

std::size_t userCount() const

How many blocks compete for this resource.

void offerFreedUnit(NodeContext& ctx)

Offers a freed unit to whichever registered user has the longest-waiting entity, so a shared resource does not favour the block that released it.

void seize(int units = 1)

Takes units. Asserts they are available; the caller must check first.

void release(int units = 1)

Returns units to the pool.

Chapter 4

Randomness

One primitive, twelve distributions, and the tests that show a generator is sound.

Everything random is built on a single `u01()` call, so a run is reproducible from one seed. Distributions may be given their own named streams, which is what lets you change a service time without the arrival pattern shifting underneath you.

EngineKind

enum class · RandomStream.hpp

Which underlying generator a `RandomStream` uses. Includes `RANDU`, kept precisely so its failure can be demonstrated.

Values MersenneTwister, LinearCongruential, Randu

RandomStream

class · RandomStream.hpp

The single source of randomness. Everything is built on one `u01()` primitive, so the whole engine is reproducible from one seed. Supports named substreams and antithetic variates.

```

unsigned seed() const
    The seed.

EngineKind engine() const
    The engine.

long long draws() const
    The draws.

void reset()
    Back to the t=0 condition. Configuration survives; run state does not.

double u01()
    The single primitive. Every distribution in the engine is built on this one call.

void setAntithetic(bool on)
    Makes the stream return 1-u instead of u, the basis of antithetic variates.

bool isAntithetic() const
    Whether antithetic.

RandomStream substream(const std::string& name) const
    A named, independent stream derived from the base seed. Naming is what keeps a stream stable as the rest of a model changes.

SimTime exponential(SimTime mean)
    One exponential sample with the given MEAN. The inversion is the only place the 1/lambda conversion happens.

SimTime uniform(SimTime low, SimTime high)
    One uniform sample on a closed interval.

SimTime normal(SimTime mean, SimTime stdDev)
    One normal sample, by the Box-Muller transform.

SimTime lognormal(SimTime logMean, SimTime logStdDev)
    One lognormal sample, from the mean and sd of the LOGARITHM.

SimTime weibull(SimTime scale, SimTime shape)
    One Weibull sample, by inversion.

SimTime erlang(SimTime meanOfEach, int phases)
    One Erlang sample: the sum of `phases' exponential draws.

SimTime triangular(SimTime low, SimTime mode, SimTime high)
    One triangular sample, by inversion either side of the mode.

int poisson(double mean)
    One Poisson count, by Knuth's multiplication method.

bool bernoulli(double p)
    True with probability p. One draw.

std::size_t uniformIndex(std::size_t n)
    A uniformly chosen index in [0, n). What the Random queue discipline uses.

static double normalQuantile(double p)
    The inverse normal CDF, used to build normal samples and confidence intervals.
```

IDistribution

class · Distribution.hpp

The interface every distribution implements: draw a value, report a theoretical mean, describe yourself, clone yourself, and optionally sample from your own stream.

```

virtual SimTime draw(RandomStream& rng) = 0
    Samples one value, using this object's own stream if it has been given one.

virtual std::string describe() const = 0
    A human-readable one-line description, used in model dumps and traces.

virtual void reset()
    Back to the t=0 condition. Configuration survives; run state does not.

virtual SimTime mean() const = 0
    The theoretical mean, used by the stability check before the run.

virtual std::unique_ptr<IDistribution> clone() const = 0
    A deep copy. Needed because a distribution may be held in two places at once.

void useStream(RandomStream* s)
    Gives every sampling site beneath this node its own random stream.

RandomStream* stream() const
    The stream.
```

Exponential

class · Distribution.hpp · inherits public IDistribution

Exponential inter-event times, parameterised by MEAN, not rate. The 1/lambda conversion happens in exactly one line.

```

explicit Exponential(SimTime mean)
    Constructor.

SimTime draw(RandomStream& rng) override
    Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
    A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
    The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
    A deep copy. Needed because a distribution may be held in two places at once.
```

Constant

class · Distribution.hpp · inherits public IDistribution

Always the same value. Consumes nothing from the random stream, which matters when comparing runs.

```

explicit Constant(SimTime value)
    Constructor.

SimTime draw(RandomStream& rng) override
    Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
    A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
    The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
    A deep copy. Needed because a distribution may be held in two places at once.
```

Uniform

class · Distribution.hpp · inherits public IDistribution

Uniform on a closed interval.

Uniform(SimTime low, SimTime high)
Constructor.

SimTime draw(RandomStream& rng) override
Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
A deep copy. Needed because a distribution may be held in two places at once.

Triangular

class · Distribution.hpp · inherits public IDistribution

Triangular with a low, a mode and a high. The usual choice when you have an expert's best, worst and likely case and no data.

Triangular(SimTime low, SimTime mode, SimTime high)
Constructor.

SimTime draw(RandomStream& rng) override
Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
A deep copy. Needed because a distribution may be held in two places at once.

Normal

class · Distribution.hpp · inherits public IDistribution

Normal, optionally truncated at zero so a duration cannot come out negative.

Normal(SimTime mean, SimTime stdDev, bool truncateAtZero = true)
Constructor.

SimTime draw(RandomStream& rng) override
Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
A deep copy. Needed because a distribution may be held in two places at once.

Lognormal

class · Distribution.hpp · inherits public IDistribution

Lognormal. Its constructor takes the mean and standard deviation of the LOGARITHM; use fromMeanAndSd() if you have the observed values instead.

Lognormal(SimTime logMean, SimTime logStdDev)
Constructor.

static std::unique_ptr<Lognormal> fromMeanAndSd(SimTime mean, SimTime sd)
Builds a Lognormal from the mean and standard deviation you observed, rather than those of the logarithm. The conversion is not

obvious and getting it wrong is silent.

SimTime draw(RandomStream& rng) override
Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
A deep copy. Needed because a distribution may be held in two places at once.

Weibull

class · Distribution.hpp · inherits public IDistribution

Weibull, by scale and shape. Common for time-to-failure.

Weibull(SimTime scale, SimTime shape)
Constructor.

SimTime draw(RandomStream& rng) override
Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
A deep copy. Needed because a distribution may be held in two places at once.

Erlang

class · Distribution.hpp · inherits public IDistribution

A sum of k exponential phases. fromMean() takes the mean you actually want.

Erlang(SimTime meanOfEachPhase, int phases)
Constructor.

static std::unique_ptr<Erlang> fromMean(SimTime totalMean, int phases)
Builds an Erlang from the total mean you want and a phase count.

SimTime draw(RandomStream& rng) override
Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
A deep copy. Needed because a distribution may be held in two places at once.

Discrete

class · Distribution.hpp · inherits public IDistribution

A finite set of values with probabilities. Takes INDIVIDUAL probabilities summing to one; Arena's DISC spelling takes cumulative ones and is converted at the grammar boundary.

Discrete(std::vector<SimTime> values, std::vector<double> probabilities)
Constructor.

SimTime draw(RandomStream& rng) override
Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
 A deep copy. Needed because a distribution may be held in two places at once.

Empirical

class · Distribution.hpp · inherits public IDistribution

Samples straight from observed data with linear interpolation between order statistics -- for when you have a hundred real service times and no idea which textbook curve produced them.

explicit Empirical(std::vector<SimTime> observations)
 Constructor.

SimTime draw(RandomStream& rng) override
 Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
 A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
 The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
 A deep copy. Needed because a distribution may be held in two places at once.

Poisson

class · Distribution.hpp · inherits public IDistribution

Counts rather than durations: arrivals per hour, defects per batch.

explicit Poisson(double mean)
 Constructor.

SimTime draw(RandomStream& rng) override
 Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
 A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
 The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
 A deep copy. Needed because a distribution may be held in two places at once.

Deterministic

class · Distribution.hpp · inherits public IDistribution

Walks a fixed list of values, optionally repeating. The basis of every hand-checkable test in this project, because it makes a run reproducible on paper.

explicit Deterministic(std::vector<SimTime> values, bool repeat = true)
 Constructor.

SimTime draw(RandomStream& rng) override
 Samples one value, using this object's own stream if it has been given one.

std::string describe() const override
 A human-readable one-line description, used in model dumps and traces.

SimTime mean() const override
 The theoretical mean, used by the stability check before the run.

std::unique_ptr<IDistribution> clone() const override
 A deep copy. Needed because a distribution may be held in two places at once.

void reset() override
 Back to the t=0 condition. Configuration survives; run state does not.

TestResult

struct · StreamTests.hpp

The outcome of one generator-quality test: a statistic, a threshold, and whether it passed.

StreamTests

class · StreamTests.hpp

Statistical tests a random stream should survive: chi-square uniformity, Kolmogorov-Smirnov, runs up and down, autocorrelation, and a 3-D serial test that exposes lattice structure.

static TestResult chiSquareUniformity(RandomStream& rng, int n, int bins = 10)

Bins many draws and compares the counts against a flat expectation. Catches a generator whose output is not evenly spread.

static TestResult kolmogorovSmirnov(RandomStream& rng, int n)
 Compares the empirical distribution against the uniform one by their largest gap. Sensitive where chi-square is not.

static TestResult runsUpAndDown(RandomStream& rng, int n)
 Counts ascending and descending runs against their expected number. Catches sequences that are uniform but not independent.

static TestResult autocorrelation(RandomStream& rng, int n, int lag = 1)
 Correlation between draws a given lag apart. A generator can pass every one-dimensional test and still fail this.

static TestResult serial3D(RandomStream& rng, int n, int binsPerAxis = 16)
 Bins consecutive triples in the unit cube. This is the test that exposes RANDU, whose triples fall on fifteen planes.

static std::vector<TestResult> runAll(RandomStream& rng, int n = 600000)
 Runs every test and collects the results.

static void report(const std::vector<TestResult>& results, const std::string& title)
 Prints a table of test results.

static double chiSquareCritical95(int degreesOfFreedom)
 The 95% critical value of chi-square, so a test can report pass or fail rather than a bare statistic.

Chapter 5

The Expression Layer

How a model's conditions, values and durations became text rather than compiled code.

Through v9 a service time was a constructed distribution and a condition was a lambda, so changing a model needed a compiler. v10 makes every one of those fields a string. There is no separate distribution field any more: EXPO(0.8) is a function in the grammar whose node owns one of the twelve IDistribution objects that already existed.

Value

A variant of double and string: what an expression evaluates to. Strings exist for one purpose, comparing an entity type. Booleans are numbers, 0 and 1, which is what lets a condition field and a duration field be the same kind of field.

Errors are data, not exceptions

A malformed expression is a person typing in a cell, not a programmer bug, so the lexer and parser never throw: they record a Diagnostic carrying a SourceSpan, recover, and keep going. One call reports many problems. The exception is `expr()`, which throws, because on the C++ API a bad expression really is a programmer error and there is no cell to point at.

ExpressionError

class · Value.hpp · inherits public ModelError

Thrown when an expression cannot do its job AT RUN TIME -- a string in arithmetic, division by zero, an attribute read with no entity.

```
explicit ExpressionError(const std::string& what) :
ModelError(what)
    Constructor.
```

SourceSpan

struct · Diagnostic.hpp

An offset and length within the text that was parsed. Carrying this from the lexer to the diagnostic is what lets a front end put a cursor on the exact bad character.

Severity

enum class · Diagnostic.hpp

Whether a diagnostic is an error or a warning.

Values Error, Warning

Diagnostic

struct · Diagnostic.hpp

A user's mistake, reported as DATA rather than thrown. The parser collects a list of these and keeps going, because a spreadsheet must show every bad cell at once and an exception can only carry one failure.

TokenKind

enum class · Lexer.hpp

The lexical categories of the expression grammar.

Values Number, Text, Identifier, Plus, Minus, Star, Slash, Percent, Caret, Bang, Less, LessEqual, Greater, GreaterEqual, EqualEqual, BangEqual, AndAnd, OrOr, LParen, RParen, Comma, End, Invalid

Token

struct · Lexer.hpp

One lexed token: its kind, its span, and its number or text.

LexResult

struct · Lexer.hpp

Everything one call to `tokenise()` produced: the tokens, always ending in End, and any diagnostics.

UnaryOp

enum class · Expression.hpp

The prefix operators: negation and logical not.

Values Negate, Not

BinaryOp

enum class · Expression.hpp

The infix operators, from arithmetic through comparison to the short-circuiting logicals.

Values Add, Subtract, Multiply, Divide, Modulo, Power, Less, LessEqual, Greater, GreaterEqual, Equal, NotEqual, And, Or

IExpression

class · Expression.hpp

A node in the parsed expression tree. Beyond `evaluate()`, the interesting members are `validate()`, which reports problems without throwing, and `meanIfKnown()`, which admits when a mean cannot be computed in advance.

```
explicit IExpression(SourceSpan span) : m_span(span)
    Constructor.
```

SourceSpan span() const

The range of source text this came from.

```
virtual Value evaluate(EvalContext& ctx) const = 0
    Computes this node's value in the given context.
```

```
virtual void validate(const ValidationContext& vc,
std::vector<Diagnostic>& out) const = 0
```

Appends every problem found. Never throws, so one call reports many.

```
virtual std::optional<double> meanIfKnown() const
```

The mean if it can be computed in advance, or nothing. Nothing means 'cannot tell', never 'zero'.

```
virtual std::string describe() const = 0
```

A human-readable one-line description, used in model dumps and traces.

```
virtual std::unique_ptr<IExpression> clone() const = 0
    A deep copy of the whole subtree.
```

```
virtual void useStream(RandomStream* s)
```

Gives every sampling site beneath this node its own random stream.

```
virtual void reset()
```

Back to the `t=0` condition between replications. Only a Deterministic distribution has anything to do, but an expression that owns one must pass it on.

LiteralExpression

class · Expression.hpp · inherits public IExpression

A number or a quoted string, known at parse time.

```
LiteralExpression(Value v, SourceSpan span) :
IExpression(span), m_value(std::move(v))
    Constructor.

const Value& value() const
    The value.

Value evaluate(EvalContext&) const override
    Computes this node's value in the given context.

void validate(const ValidationContext&,
std::vector<Diagnostic>&) const override
    Appends every problem found to the list. Does not throw and does not
    stop at the first.

std::optional<double> meanIfKnown() const override
    The mean if it can be computed in advance, or nothing. Nothing means
    'cannot tell', never 'zero'.

std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.

ExpressionPtr clone() const override
    A deep copy. Needed because a distribution may be held in two places
    at once.
```

NameExpression

class · Expression.hpp · inherits public IExpression

A bare name, resolved LATE -- the parser stores only the text, and whether it is an attribute, a variable, Entity.Type or TNOW is decided at validation and evaluation. That is what stops the parser going stale as new kinds of name are added.

```
const std::string& name() const
    The text the parser captured, still unresolved.

Value evaluate(EvalContext& ctx) const override
    Computes this node's value in the given context.

void validate(const ValidationContext& vc,
std::vector<Diagnostic>& out) const override
    Appends every problem found to the list. Does not throw and does not
    stop at the first.

std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.

ExpressionPtr clone() const override
    A deep copy. Needed because a distribution may be held in two places
    at once.
```

UnaryExpression

class · Expression.hpp · inherits public IExpression

A prefix operator applied to one operand.

```
Value evaluate(EvalContext& ctx) const override
    Computes this node's value in the given context.

void validate(const ValidationContext& vc,
std::vector<Diagnostic>& out) const override
    Appends every problem found to the list. Does not throw and does not
    stop at the first.

std::optional<double> meanIfKnown() const override
    The mean if it can be computed in advance, or nothing. Nothing means
    'cannot tell', never 'zero'.

std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.

ExpressionPtr clone() const override
    A deep copy. Needed because a distribution may be held in two places
    at once.

void useStream(RandomStream* s) override
    Gives every sampling site beneath this node its own random stream.

void reset() override
    Back to the t=0 condition. Configuration survives; run state does not.
```

BinaryExpression

class · Expression.hpp · inherits public IExpression

An infix operator over two operands. The logical operators short-circuit, which is what makes a guarded division safe to write.

```
Value evaluate(EvalContext& ctx) const override
    Computes this node's value in the given context.

void validate(const ValidationContext& vc,
std::vector<Diagnostic>& out) const override
    Appends every problem found to the list. Does not throw and does not
    stop at the first.

std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.

ExpressionPtr clone() const override
    A deep copy. Needed because a distribution may be held in two places
    at once.

void useStream(RandomStream* s) override
    Gives every sampling site beneath this node its own random stream.

void reset() override
    Back to the t=0 condition. Configuration survives; run state does not.
```

LambdaExpression

class · Expression.hpp · inherits public IExpression

Adapter wrapping a C++ predicate so the pre-v10 std::function API is a constructor for the one representation rather than a second code path.

```
Value evaluate(EvalContext& ctx) const override
    Computes this node's value in the given context.

void validate(const ValidationContext&,
std::vector<Diagnostic>&) const override
    Appends every problem found to the list. Does not throw and does not
    stop at the first.

std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.

ExpressionPtr clone() const override
    A deep copy. Needed because a distribution may be held in two places
    at once.
```

DistributionExpression

class · Expression.hpp · inherits public IExpression

Adapter wrapping an IDistribution so the pre-v10 API keeps working. Also what a parsed EXPO(0.8) with constant arguments becomes.

```
Value evaluate(EvalContext& ctx) const override
    Computes this node's value in the given context.

void validate(const ValidationContext&,
std::vector<Diagnostic>&) const override
    Appends every problem found to the list. Does not throw and does not
    stop at the first.

std::optional<double> meanIfKnown() const override
    The mean if it can be computed in advance, or nothing. Nothing means
    'cannot tell', never 'zero'.

std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.

ExpressionPtr clone() const override
    A deep copy. Needed because a distribution may be held in two places
    at once.

void useStream(RandomStream* s) override
    Gives every sampling site beneath this node its own random stream.

void reset() override
    Back to the t=0 condition. Configuration survives; run state does not.
```

ParseResult

struct · Parser.hpp

What parsing produced: a tree, and the diagnostics found on the way. The tree is never null; on error it holds a placeholder that is never evaluated.

IModelState

class · EvalContext.hpp

The four questions an expression may ask about a running system, plus the clock. Declared by the expression layer and implemented by SimulationSystem, so the expression layer never has to include Model.hpp.

```
virtual double queueLength(const std::string& blockName)
const = 0
    How many entities are waiting at a named block. Throws on an
    unknown name rather than reading as an empty queue.
virtual double resourceBusy(const std::string& name) const =
0
    Units of a named resource currently seized.
virtual double resourceCapacity(const std::string& name)
const = 0
    A named resource's capacity.
virtual double numberInSystem() const = 0
    How many entities are anywhere in the system.
virtual SimTime now() const = 0
    The current simulation time.
```

EvalContext

class · EvalContext.hpp

The only view of the engine an expression gets while a run is happening: the current entity, the variables, the model state and the random stream. Any of them may be absent, and each accessor says so rather than returning a plausible default.

```
const Entity* entity() const
    The entity.
VariableStore* variables() const
    The variables.
const IModelState* state() const
    The state.
RandomStream* rng() const
    The rng.
double attribute(const std::string& name) const
    Reads an entity attribute, throwing if there is no entity rather than
    returning zero.
const std::string& entityType() const
    The current entity's type name.
RandomStream& requireRng() const
    The random stream, or an error explaining that none was supplied.
const IModelState& requireState() const
    The live model state, or an error explaining that none was supplied.
```

FieldContext

enum class · EvalContext.hpp

Whether the field being validated has an entity to read from. A Create block's interarrival time is evaluated before its entity exists, so an attribute reference there is an error caught before the run.

Values HasEntity, NoEntity

ValidationContext

struct · EvalContext.hpp

What a name is allowed to resolve to, checked before the run: the declared variables and attributes, and whether an entity is available.

```
bool isVariable(const std::string& name) const
    Whether this name is a declared variable.
```

```
bool isAttribute(const std::string& name) const
    Whether this name is a declared attribute.
```

VariableStore

class · VariableStore.hpp

Arena's Variable data module. Global, numeric, time-persistent values that belong to the system rather than to any entity. A variable may not share a name with an attribute, and writing an undeclared one throws.

```
void declare(const std::string& name, double initialValue)
    Declares a variable with an initial value. Refuses a duplicate, and
    refuses a name already used by an attribute.
void noteAttributeNames(std::vector<std::string> names)
    Supplies the attribute names that declare() checks against.
bool has(const std::string& name) const
    Whether a variable of this name exists.
double get(const std::string& name) const
    The current value.
void set(const std::string& name, double value, SimTime now)
    Closes the time integral at `now`, then changes the value. Throws on
    an undeclared name, so a typo cannot become a second variable.
void reset()
    Back to the t=0 condition. Configuration survives; run state does not.
void resetStatistics(SimTime now)
    Discards measurements collected so far and starts again from now,
    without touching what is held. This is warm-up removal at block level.
void updateIntegrals(SimTime now)
    Closes every variable's integral up to now.
double timeAverage(const std::string& name) const
    The time-weighted average since measurement began.
const std::vector<std::string>& names() const
    The variables, in declaration order.
std::size_t count() const
    How many entities have passed through.
```

Chapter 6

The Document Layer

How a model stopped being a program and became a set of spreadsheets.

v10 made a model's fields text; v11 makes the model itself data. Every module type publishes its columns through ModuleRegistry, a ModelDocument holds rows of those cells as text, the .des reader and writer round-trip them byte for byte, and compile() turns a document into a Model or into diagnostics that point at individual cells. The engine never learns what a document is.

Why a document is not a Model

A Model must always be valid: a route names a block that exists, a Process names a resource that was declared. A document being edited is none of those things - it is half-finished and contradictory most of the time it is open. Two types, therefore, and one direction of travel between them.

Rows are addressed by position

Never by a stable id, because the two disagree the moment a row moves - and row order is semantic here. A Decide takes the first branch that matches and an Assign runs its fields in order, so reordering two rows changes what the model does.

Four passes, all of which run

Schema, then references, then expressions, then structure. Every pass runs even when an earlier one found errors, because the point of the layer is to report every bad cell rather than the first. The structure pass is the one exception: it cannot run with broken references, so it is skipped and structureChecked says so.

ColumnType

enum class · ModuleSchema.hpp

What kind of value a column holds: Text, Identifier, Integer, Real, Boolean, Enum, Expression or Reference. The schema pass checks a cell against this, and a front end picks an editor from it.

Values Text, Identifier, Integer, Real, Boolean, Enum, Expression, Reference

ModuleKind

enum class · ModuleSchema.hpp

Whether a module is Data (a Resource, a Variable), Flowchart (a block entities pass through), or Child (a row belonging to another row, such as one branch of a Decide).

Values Flowchart, Data, Child

Column

struct · ModuleSchema.hpp

One column of a module's spreadsheet: its name, type, whether it is required, its default, the values an Enum allows, and for a Reference the module type it must name. 'Block' is the pseudo-target meaning any flowchart block, which is what an exit column points at.

ModuleSchema

struct · ModuleSchema.hpp

Everything a front end needs to render one module type: its name, its kind, its columns, whether it is read-only, and for a child table the column naming its parent. Queue is the one read-only schema, because this engine has no queue object apart from its Process.

const Column* column(const std::string& id) const

The named column, or null.

ModuleRegistry

class · ModuleSchema.hpp

The published set of schemas, a singleton built once at startup. A front end asks it what module types exist and what columns each has, so a module added in a later version renders without the front end changing.

static const ModuleRegistry& instance()

The one registry. Built on first use from buildSchemas().

const ModuleSchema* find(const std::string& typeName) const

The schema for a module type, or null. Null is not an error: an unknown type is preserved and warned about, never dropped.

const std::vector<ModuleSchema>& all() const

Every schema, in the order a front end should list them.

ModelDocument

class · ModelDocument.hpp

Rows of text cells, grouped by module type and addressed by POSITION. Unlike a Model it may be invalid, half-finished and contradictory, which is what makes it editable. It also keeps the source lines it was read from, so writing it back reproduces the file byte for byte.

const std::vector<std::string>& types() const

Every module type present, in the order they first appeared. The build pass follows this, so it is the order blocks are created in.

std::size_t rowCount(const std::string& type) const

How many rows a module type has.

const std::vector<Row>& rows(const std::string& type) const

Every row of a module type, in file order. Order is semantic: a Decide takes the first branch that matches, an Assign runs its fields in order.

Row& addRow(const std::string& type)

Appends an empty row to a module type's table and returns its position.

void removeRow(const std::string& type, std::size_t index)

Deletes a row by position. Every later row shifts down, which is why nothing holds a row index across an edit.

void moveRow(const std::string& type, std::size_t from, std::size_t to)

Moves a row to another position. It exists because row order is part of the model, not a display preference.

void setSourceLines(std::vector<std::string> lines)

Sets the source lines.

void setPreamble(std::vector<std::string> lines)

Sets the preamble.

void setTrailer(std::vector<std::string> lines)

Sets the trailer.

const std::vector<std::string>& preamble() const

The preamble.

const std::vector<std::string>& trailer() const

The trailer.

Row& rowAt(const std::string& type, std::size_t index)

One row, mutable, by type and position. It exists for the reader, which fills in a row source block after parsing the record.

const std::vector<std::string>& sourceLines() const

The source lines.

bool edited() const

The edited.

void markEdited()

Performs mark edited.

ReadResult

struct · DocumentFormat.hpp

What reading a .des file produces: the document, the diagnostics found while reading it, and the format version the file declared. Reading never throws -- a malformed line becomes a diagnostic and reading continues.

CellRef

struct · Diagnostic.hpp

Which cell a diagnostic came from: module type, row position, column name. It composes with v10's SourceSpan rather than replacing it, so the character offset the parser measured survives inside the cell the compiler names.

CompileResult

struct · Compiler.hpp

What compiling a document produces: a Model when it succeeded, the diagnostics either way, and whether the structural pass actually ran. That last flag matters because the structure pass cannot run with broken references, and reporting a model as checked when it was not is the failure this project keeps refusing.

Chapter 7

Runtime Control

How a run stopped being something you wait for and became something you drive.

`SimulationSystem::run()` blocks until the stopping rule is met, which is the right shape for a program and the wrong one for a front end: there is no moment at which it can redraw, and no way to stop. `v12` splits that loop. `stepOnce()` does one event, `RunController` owns the loop around it and the replication loop above that, and `run()` becomes a loop over `stepOnce()` and nothing else -- the same loop, with the caller holding the handle.

Why stepping and not threads

The engine's entire claim is that one seed gives one run. A thread buys responsiveness that a stepped loop already provides, and pays for it with a lock between the clock and the statistics and a class of bug that no byte-identical gate can reliably reproduce. Pausing is not calling; cancelling is not calling ever again.

Watching must not change the run

A snapshot is built when it is asked for, from accessors that already existed. Nothing is added to the inner loop, so a run is bit-for-bit identical whether or not anyone was watching -- which is asserted rather than assumed, and which a watcher that consumed a single random number was shown to break.

Progress that admits it cannot tell

`ITerminationRule::progress()` returns an optional, and nothing means CANNOT TELL rather than zero. A time limit divides; the drained-system rule has no override at all, because whether a system will next be empty is not knowable in advance. A bar that reads 0% for a whole run and then jumps to 100% is a lie the caller has no way to detect.

One replication loop

`RunController` owns the loop over replications, and `Experiment` is a wrapper over it. Two loops would have had to agree about seeding, antithetic pairing, warm-up and the observation grid, and the one that drifts is always the one nobody runs. Antithetic pairing is where the abstraction leaks: one replication is two runs, so a progress fraction restarts at zero halfway through.

RunState

enum class · RunController.hpp

Where a run has got to: Ready, Running, Paused, Finished, Cancelled or Failed. Finished and Cancelled are terminal, and `advance()` on either returns 0 rather than throwing -- a front end that polls past the end is normal, not wrong.

Values Ready, Running, Paused, Finished, Cancelled, Failed

RunProgress

struct · RunController.hpp

What a watcher reads between calls: which replication, the clock, how many events have been processed, and a fraction that MAY BE ABSENT. Absent means the stopping rule cannot tell how far through it is, which is not the same as zero.

BlockSnapshot

struct · RunController.hpp

One flowchart block at an instant: its queue length, how many it has served, and its utilisation over the measured period.

ResourceSnapshot

struct · RunController.hpp

One resource at an instant: how many units are busy, out of how many it has.

VariableSnapshot

struct · RunController.hpp

One declared variable and its current value.

RunSnapshot

struct · RunController.hpp

The whole running system at an instant -- clock, arrivals, departures, number in system, and one entry per block, resource and variable. Built ON DEMAND from accessors that already existed, so nothing is added to the inner loop and a run is bit-for-bit identical whether or not anyone was watching.

RunSetup

struct · RunSetup.hpp

How to run a model: length, warm-up, replications, base seed, and the stopping conditions. Read from the [Run] module, so a model file carries its own run length rather than depending on a number stored somewhere else.

RunController

class · RunController.hpp

The run, with the loop handed to the caller. `advance(budget)` does at most that many events and returns; pausing is not calling, cancelling is not calling ever again. It owns the replication loop too, which is why `Experiment` builds on it rather than keeping a second implementation.

RunController(RunSetup setup, ModelBuilder build)
Constructor.

~RunController()
Destructor.

RunState state() const
The state.

const std::string& failure() const
Why the run Failed, when it did.

std::size_t advance(std::size_t maxEvents)

Does at most `maxEvents` events, rolling on to the next replication when one ends, and returns how many it actually did. Zero when paused, finished, cancelled or failed. A model error part way through a run -- SQRT of a negative number, a service time that comes out negative -- marks the run Failed with that message instead of propagating. Until 15.1 it went out through every caller, and in the terminal UI that ended the program.

void pause()
Running becomes Paused, and `advance()` then does nothing.

void resume()
Paused becomes Running. It cannot undo a cancel.

void cancel()
Stops for good. The run so far stays readable.

RunProgress progress() const
A `RunProgress` for the moment it is called.

RunSnapshot snapshot() const

A RunSnapshot of the replication in progress, or an empty one between replications.

void report(std::ostream& os) const

One replication prints the run own report; several print confidence intervals, because quoting one number out of thirty runs is what Experiment exists to stop.

const std::vector<ReplicationResult>& results() const

One ReplicationResult per completed replication.

const std::vector<std::vector<double>>& series() const

The series.

void runToCompletion()

Drives to the end. Loops on STATE rather than on the count advance() returns: a replication that produced no events would return 0 and strand a caller that trusted that count.

RegressionOutcome

struct · Regression.hpp

What happened to one model in a regression run: whether it matched, and if not, the first line where it differed.

RegressionReport

struct · Regression.hpp

The verdict over a whole manifest. ok() is false when nothing was checked, because a gate that measured nothing has not passed -- it has not run.

bool ok() const

The ok.

Chapter 8

The Terminal UI

How the spreadsheets got a screen, and how a terminal interface is tested.

v10 made a model's fields text, v11 made the model itself data, and v12 made the run something a caller drives. Each was built for a front end that did not exist. This is that front end -- a tab bar of module types, a grid of rows, a detail pane where editing happens, and a run view.

The screen is a value

A renderer fills a Screen; the terminal blits it. `render()` is pure and `handleKey()` touches nothing outside the state, so a test builds a document, types a scripted key sequence, and asserts on the screen AS TEXT -- no terminal, no timing, no sleeps. That is what makes a terminal interface testable at all.

Why the portable half lives in src/

The verification script compiles `src/*.cpp`, and its sanitiser `leg` compiles tests and `src` together. Putting the portable half of the interface there runs the whole of it through both compilers and both sanitisers with no change to any gate script. Only the platform layer sits outside, in `tui/`, and platform code cannot be tested anyway -- which is the reason it is three methods long.

Nothing here names a module type

The tab bar is every type the registry publishes, then any the document holds that it does not. The first half is why a module added in a later version renders without this code changing. The second is why a file written by a later version shows its unknown modules instead of hiding them.

What only looking at it found

Six layout bugs passed every assertion in the suite, because each of them passes a search of the screen text: the selected tab drawn off the edge, a file name trimmed from the wrong end, a detail pane that did not scroll, an enum hint that ran on from the value, text overflowing the frame, and a finished run reporting that its rule could not say how far along it was. The screen-as-a-value design makes rendering testable; it does not make it self-evaluating.

Building one, rather than editing one

v13 could open, edit, save and run a model; it could not be sat down in front of cold. v14 is that: every column carries a line saying what it is for, in the SCHEMA rather than here, because the schema is what a front end reads in order to render and a second front end would need the same sentence. Enter on an enum or a reference opens a list built from `referenceCandidates()` -- the same function the compiler's reference pass is written in terms of, so a list cannot offer a name that is then rejected.

Escape in that list does not cancel. It drops into the text editor, because naming a block BEFORE that block exists is the ordinary way a model gets built and no list can offer that. A second Escape abandons. The list is for when you know, and it gets out of the way the instant you do not.

The flow view reads cells, not a Model

`flowOf()` walks the document rather than a compiled Model, because a document with a dangling exit does not compile and that is exactly when the shape is hardest to hold in your head. It also lists a Decide's branches in the order they are tried, with its Next shown last as the else exit -- printed first, as it was at first, it read as the default path being tried first, which is the opposite of what happens.

Attr

enum class · Screen.hpp

How a glyph is drawn: normal, bold, dim, reversed, or the red used for a diagnostic. The terminal turns these into escape sequences; nothing above it knows that.

Values Normal, Bold, Dim, Reverse, Error

Screen

class · Screen.hpp

A grid of glyphs, and the decision the whole user interface rests on. A renderer fills one and the terminal blits it, so a test can render a document and assert on the text a person would read -- headless, with no timing and no sleeps. Writes outside its bounds are dropped rather than asserted: a renderer that computes one column too far has a layout bug, and a missing character is a better way to find out than a crash in front of the user.

Screen(int width, int height)

Constructor.

int width() const

The width.

int height() const

The height.

void clear()

Performs clear.

void put(int x, int y, char ch, Attr attr = Attr::Normal)

One glyph. Out of range is dropped, not an error.

int text(int x, int y, const std::string& s, Attr attr = Attr::Normal)

A run of text, returning the x it stopped at so callers can chain runs.

void hline(int x, int y, int length, char ch = '-', Attr attr = Attr::Normal)

A horizontal run of one character.

void box(int x, int y, int width, int height, Attr attr = Attr::Normal)

A frame drawn in dashes, pipes and plus signs.

const Glyph& at(int x, int y) const

The glyph at a position, or a blank one when the position is outside the screen.

std::string line(int y) const

One row as plain text with the trailing blanks trimmed. This is the test interface: an assertion says what a person would read rather than picking through an attribute grid.

std::string asText() const

Every line, newline separated. What a test compares.

KeyKind

enum class · Key.hpp

What kind of keypress this is: a printable character, a control chord, or one of the named keys a terminal sends as an escape sequence.

Values Char, Enter, Escape, Backspace, Delete, Tab, BackTab, Up, Down, Left, Right, Home, End, PageUp, PageDown, Ctrl, Function, Mouse, Unknown

Key

struct · Key.hpp

A keypress as a value. The platform layer turns a console record or an escape sequence into one of these, and everything above takes them -- which is what lets a test type a whole session without a terminal. Control keys normalise to upper case, so ^s and ^S are one key rather than two that can disagree.

```
static Key character(char c)
    A printable key.

static Key control(char c)
    A control chord, normalised to upper case.

static Key special(KeyKind kind)
    One of the named keys, such as Up or Enter.

static Key shifted(KeyKind kind)
    An arrow or a Home/End with Shift held, which is what extends a
    selection. Shift rides ALONGSIDE the kind rather than doubling it, so
    there is one Left in every switch rather than two that can disagree.

static Key function(int n)
    A function key, carrying its number. F1 opens the key map.

static Key mouse(MouseButton button, int x, int y)
    A click or a wheel turn at a screen position. Screen coordinates, so the
    renderer's layout decides what was hit -- the terminal layer does not
    know what a palette is.

bool isWheel() const
    Whether wheel.
```

MouseButton

enum class · Key.hpp

Which button, or which way the wheel turned. A click arrives as a Key like any other press, so there is one event stream and nothing has to merge two.

Values None, Left, Right, Middle, WheelUp, WheelDown

TerminalSize

struct · Terminal.hpp

How many columns and rows the terminal has right now. Read every frame, because a person can resize a window mid-edit.

ITerminal

class · Terminal.hpp

The only platform code in the project: report the size, blit a Screen, read a Key, say whether one is waiting, and name the window. It is an object rather than a handful of functions because its destructor restores the console -- a return from anywhere in the loop must not leave somebody in raw mode with no cursor. openTerminal() can refuse, with a reason: a console that was not a console used to be driven anyway, and the loop then spun forever reading nothing.

```
virtual TerminalSize size() const = 0
    The terminal size right now.

virtual void present(const Screen& screen) = 0
    Write a whole Screen. No diffing: a spreadsheet is a few thousand cells
    and a person types at human speed, so the optimisation would only be
    somewhere for a rendering bug to hide.

virtual Key nextKey() = 0
    Block until a key arrives. Anything unrecognised comes back as
    Unknown, which the input layer ignores -- an unfamiliar escape
    sequence must never stop the program.

virtual bool keyPending() = 0
    Is a keypress waiting? The fourth method, and the one that makes a
    run interruptible: while a simulation is advancing the loop must not
    block in nextKey(), or Escape is never seen and an unbounded model
    runs until the process is killed. On Win32 it also DRAINS the mouse,
    focus and resize records the console reports alongside keys --
    otherwise the handle stays signalled and the run never advances at all,
    the same bug wearing the opposite face.

virtual void setTitle(const std::string& title) = 0
```

Names the window after the file that is open. With two models open, every window used to say the same thing, and a person could not tell which was which.

FlowBlock

struct · TuiState.hpp

One flowchart block as the flow view shows it: its name, its type, and where its exits lead. Built from the DOCUMENT rather than from a compiled Model, because a document with a dangling exit does not compile -- and that is exactly when somebody needs to see the wiring. It also carries whether an exit names nothing and whether anything arrives here, neither of which is an error on its own and neither of which is said anywhere else.

TuiState

class · TuiState.hpp

Everything the user interface knows: the document, where the cursor is, which mode is active, the diagnostics from the last compile, the undo stack and the run in progress. The renderer reads it and the input layer writes it, and neither touches a terminal.

```
static TuiState open(const std::string& path)
    Reads a file. One that does not PARSE still opens, with its diagnostics
    shown, because the document layer preserves what it read. One that
    does not EXIST opens as an empty document, so pointing the editor at
    a new name starts a new model; the status line says which happened,
    because empty and unreadable must not look alike.

static TuiState fromText(const std::string& text,
std::string path)
    A state around text already in memory rather than a file on disk. The
    tests use it so the suite does not need a file for every case, and so a
    test that SAVES cannot accidentally depend on what a previous run
    left at that path.

View view() const
    The view.

Pane focus() const
    The focus.

Overlay overlay() const
    The overlay.

void setView(View v)
    Sets the view.

void setFocus(Pane p)
    Sets the focus.

void setOverlay(Overlay o)
    Sets the overlay.

const std::string& path() const
    The path.

bool dirty() const
    The dirty.

const std::string& status() const
    The status.

void setStatus(std::string s)
    Sets the status.

const TextBuffer& buffer() const
    The text being edited. The non-const overload is how the input layer
    moves the caret and extends selections; anything that CHANGES the
    text goes through the editing members instead, so nothing can alter it
    without the document and the diagnostics catching up.

TextBuffer& buffer()
    The text being edited. The non-const overload is how the input layer
    moves the caret and extends selections; anything that CHANGES the
    text goes through the editing members instead, so nothing can alter it
    without the document and the diagnostics catching up.

void edited()
    Performs edited.

void insertText(const std::string& text)
    Inserts text at the caret, replacing the selection, and re-reads. What a
    paste and the starter model both go through.

void typeChar(char c)
```

One character at the caret. Every keystroke re-parses and re-compiles, which for a file measured in kilobytes costs nothing worth measuring -- and which is why the compiler has to survive every half-typed prefix.

```
void newline()
    Performs newline.

void backspace()
    Performs backspace.

void del()
    Performs del.

void undo()
    Pops a whole-document snapshot. It leaves the document dirty on purpose -- undoing back to what is on disk is not the same as knowing you are there, and claiming otherwise loses work.

void redo()
    Performs redo.

void cut()
    Performs cut.

void copy()
    Performs copy.

void paste()
    Performs paste.

const std::string& clipboard() const
    The clipboard.

void setClipboard(std::string s)
    Sets the clipboard.

bool save()
    Writes the document back. Records nobody edited come out exactly as they were read, comments included.

bool save(const std::string& toPath)
    Writes the document back. Records nobody edited come out exactly as they were read, comments included.

const ModelDocument& document() const
    The document.

const std::vector<Diagnostic>& diagnostics() const
    The diagnostics.

const Diagnostic* diagnosticOnLine(std::size_t line) const
    The first diagnostic on a 1-based file line, or null. An ERROR beats a warning on the same line: one marker per line, and the one worth showing is the one that stops the model running.

std::size_t firstErrorLine() const
    The first error line.

void goToFirstError()
    Performs go to first error.

const std::vector<std::string>& palette() const
    The palette.

std::size_t paletteIndex() const
    The palette index.

void stepPalette(long long delta)
    Moves the selection in the module palette. Clamps rather than wraps, like every other cursor here.

void setPaletteIndex(std::size_t i)
    Sets the palette index.

void insertSelectedModule()
    Performs insert selected module.

void showModuleHelp()
    Performs show module help.

void showFieldHelp()
    Performs show field help.

const std::string& helpTitle() const
    The help title.

const std::vector<std::string>& helpBody() const
    The help body.

void clearHelp()
    Performs clear help.

bool openPicker()
    Arena's drop-down, on the `key = value` line the caret is on. An Enum offers its spellings; a Reference offers what exists, built by the same function the compiler's reference pass checks against, so a list cannot offer a name that is then rejected. Returns false, having opened nothing, when the field has no list or when nothing has been declared yet -- and says why, because on a model being built from scratch that is the ordinary case.
```

```
const std::vector<std::string>& choices() const
    The choices.

std::size_t choice() const
    The choice.

void stepPicker(long long delta)
    Moves the cursor in the open list. Clamps rather than wraps.

void commitPicker()
    Performs commit picker.

void cancelPicker()
    Performs cancel picker.

const std::vector<std::string>& runs() const
    The runs.

std::size_t runIndex() const
    The run index.

void stepRun(long long delta)
    Chooses among the [Run] records the file holds. v15 allows several; v11 through v14 reported the second as an error.

void setRunIndex(std::size_t i)
    Sets the run index.

void addRunBlock()
    Performs add run block.

void startRun()
    Compiles and enters the run mode, or refuses with a reason. Entering a run mode with nothing running is worse than not entering it.

void advanceRun()
    Does a budget of events and captures the report when the run ends.

void stopRun()
    Cancels and returns to the grid.

const RunController* running() const
    The running.

const std::string& results() const
    The results.

const std::string& resultsOf() const
    The results of.

bool haveResults() const
    The have results.

std::size_t resultsScroll() const
    The results scroll.

void scrollResults(long long delta)
    Scrolls the report. A report longer than the window is the normal case for a study with replications.

bool saveResults()
    Writes the last report beside the model, as .results.txt, with a first line naming the file and WHICH RUN produced it. A report that does not say which settings made it is a report you cannot file.

const std::string& resultsPath() const
    The results path.

std::size_t flowCursor() const
    The flow cursor.

void stepFlow(long long delta)
    Moves the marker in the flow view. Enter then opens the block it rests on, which is what makes the view a way of getting somewhere rather than a second place to look.

void gotoFlowBlock()
    Performs goto flow block.

bool wantsQuit() const
    The wants quit.

void requestQuit()
    Performs request quit.
```

Chapter 9

Editing a Model

The text editor, the palette, and why the file itself is what gets edited.

v13 put a spreadsheet grid on the screen and edited a ModelDocument. v15 edits the FILE and parses it, which is the other way round and settles three things at once: the byte-identical round trip is free rather than a guarantee to keep, a value can only be wrong in one place, and comments and ordering are ordinary text a person edits rather than data a writer has to be careful with.

Every keystroke compiles

The buffer changes, the text is re-read, the document is re-compiled, and the diagnostics are re-hung on their lines. That is affordable at this size -- and it means every PREFIX of every model anyone types is a state the compiler sees. EXPO(is one of them, on the way to EXPO(1.0), and for four versions it aborted the program: Exponential asserted on a non-positive mean where six of the nine distributions threw a ModelError, and buildCall's catch, which exists precisely so a bad parameter becomes a diagnostic, cannot catch an assert.

A diagnostic names a cell; an editor needs a line

lineOf() is the join. A reader diagnostic carries its line already; a compiler diagnostic carries a CellRef, and a cell knows where it was read from; a diagnostic about a field that is NOT THERE has no cell at all, so the record's headerLine is the nearest true thing. It returns 0 for 'cannot say', and the renderer draws no marker rather than guessing -- which is the same rule as a progress bar that will not pretend to know.

One layout, two readers

layoutFor() computes the geometry once. render() draws with it and the input layer hit-tests clicks with it, so a click is turned back into what was clicked by the arithmetic that drew it.

TextBuffer

class · TextBuffer.hpp

The text of a .des file, with a caret, a selection and an undo stack. v15's whole design rests on this being the source of truth: the document, the diagnostics, the flow and the list of runs are all re-derived from it after every change, so what is saved is exactly what was typed and the byte-identical round trip costs nothing to keep.

TextBuffer()

Constructor.

explicit TextBuffer(const std::string& text)

Constructor.

void setText(const std::string& text)

Sets the text.

std::string text() const

The text.

const std::vector<std::string>& lines() const

The lines.

std::size_t lineCount() const

The line count.

const std::string& lineAt(std::size_t i) const

One line, or an empty string past the end. Out of range returns rather than throws: a renderer that computes one line too far has a layout bug, and a crash in front of the user is a worse way to find out.

Caret caret() const

The caret.

void moveTo(Caret to, bool extend = false)

Puts the caret at a position, clamping it into the text. With extend it keeps the selection anchor where it was, which is what Shift+click and Shift+arrow do.

void moveBy(long long lines, long long columns, bool extend = false)

Moves the caret by lines and columns. Off either end of a line steps to the next or the previous one, which is what makes Left at column 0 useful.

void moveToLineStart(bool extend = false)

Home.

void moveToLineEnd(bool extend = false)

End.

void moveToStart(bool extend = false)

To the top of the text.

void moveToEnd(bool extend = false)

To the end of the text, which is where a new record is appended.

bool hasSelection() const

Whether selection.

Caret selectionStart() const

The selection start.

Caret selectionEnd() const

The selection end.

void selectAll()

Performs select all.

void clearSelection()

Performs clear selection.

std::string selectedText() const

The selected text.

void insert(const std::string& text)

Inserts text at the caret, replacing the selection first. Text carrying newlines splits the line, so a paste behaves exactly like typing -- and a clipboard almost always carries them.

void newline()

Performs newline.

void backspace()

Performs backspace.

void del()

Performs del.

bool deleteSelection()

Removes the selection and joins what is left, returning false when there was none.

void insertLines(const std::vector<std::string>& block)

A block of whole lines, which is what the module palette inserts. It lands on a LINE BOUNDARY -- a partly-typed line is split rather than cut through, since a [Create] record dropped into the middle of an expression would leave two broken lines -- and the caret ends on the block's first field rather than on its header, so every insertion does not start with the same two keystrokes.

bool canUndo() const

The can undo.

bool canRedo() const

The can redo.

void undo()

Performs undo.

void redo()

Performs redo.

void checkpoint()

Performs checkpoint.

Caret

struct · TextBuffer.hpp

A position in a TextBuffer: a line and a column, both counted from zero. A column may equal the line's length, which is the position after the last character and where typing usually happens.

View

enum class · TuiState.hpp

What fills the body of the window -- the model, the flow, the runs or the results. Each is reachable from the bar across the top AND from one control key, because a bar you can only reach with a mouse is a bar half the people using it cannot reach at all.

Values Model, Flow, Runs, Results

Pane

enum class · TuiState.hpp

Which half of the Model view has the keyboard: the module palette on the left or the text on the right.

Values Palette, Editor

Overlay

enum class · TuiState.hpp

Something drawn OVER the view, which takes every key until it closes -- the key map, a field's help, a pick list, the confirm prompt, or a run in progress. Modal on purpose: a list of choices you could edit underneath would be answering a question about text that had moved.

Values None, Help, Picker, Confirm, Running

Layout

struct · TuiRender.hpp

Where everything is on screen. ONE function computes it, the renderer draws with it and the input layer hit-tests with it -- because a click has to be turned back into 'the third palette entry' by exactly the arithmetic that put it there. Two copies of that arithmetic is a bug this project has already had once, when v13's tab bar measured without the scroll markers and drew with them.

Chapter 10

The Flowchart

The blocks entities move through, and the narrow window each one gets on the engine.

A model is a graph of blocks. Each does one job to an entity and decides where it goes next. A block reaches the engine only through NodeContext, which exposes what a block may do and nothing else: it cannot touch the future event list, the statistics or the clock.

NodeContext

class · Node.hpp

The narrow facade through which a block touches the engine. A node can create, route, schedule and destroy, and cannot reach the future event list, the statistics or the clock.

```
explicit NodeContext(SimulationSystem& sim) : m_sim(sim)
    Constructor.

SimTime now() const
    The current simulation time.

RandomStream& rng()
    The shared random stream.

Trace& trace()
    The trace writer.

void route(Entity* e, INode* to)
    Hands the entity to the next block. A null target means it leaves the
    system.

void scheduleReturn(SimTime at, Entity* e, INode* node)
    Asks to be called back at a given time with this entity -- how a Process
    schedules the end of a service without seeing the event list.

void scheduleRenegadeCheck(SimTime at, Entity* e, INode* node)
    Schedules a patience timer.

void scheduleNextArrival(SimTime at, INode* source)
    A source asking to produce again. A separate call because the event
    type differs.

void setEntityType(Entity* e, const std::string& type)
    Retypes an entity through the engine, so the per-type counts move
    with it.

EvalContext evaluationContext(const Entity* e)
    Builds the EvalContext an expression needs. The only route by which a
    block reaches the variables and the model state.

VariableStore& variables()
    The global variable store.

Entity* createEntity()
    Makes a new entity.

void registerArrival(Entity* e)
    Marks an entity as demand the system received. Only a Create block
    calls it; batch representatives and duplicates are manufactured, not
    arrivals.

void destroy(Entity* e)
    Destroys an entity.
```

INode

class · Node.hpp

A block in the flowchart. Does one job to an entity and decides where it goes next. Everything from Create to Dispose is one of these, which is why the engine has no special case for arrivals.

```
explicit INode(std::string name) : m_name(std::move(name))
    Constructor.

const std::string& name() const
    The name this object was constructed with.

INode* next() const
    The default onward block.

virtual void setNext(INode* n)
    Sets the block this one routes to by default.
```

```
virtual void enter(NodeContext& ctx, Entity* e) = 0
    An entity has arrived at this block. Does the block's job and routes
    onward -- possibly not immediately.

virtual void onScheduledEvent(NodeContext& ctx, Entity* e)
    A previously scheduled return has come due, such as the end of a
    service or a delay.

virtual void onRenegadeTimeout(NodeContext& , Entity* /*e*/)
    A patience timer has expired. Timers are never cancelled, so this
    checks whether the entity is still waiting and ignores the event if not.

virtual void reset()
    Back to the t=0 condition. Configuration survives; run state does not.

virtual void resetStatistics(SimTime )
    Discards measurements collected so far and starts again from now,
    without touching what is held. This is warm-up removal at block level.

virtual std::string describe() const = 0
    A human-readable one-line description, used in model dumps and
    traces.

virtual double loadPerVisit() const
    Mean resource-time consumed per entity passing through, divided by
    capacity. Used by the stability check.

virtual bool loadIsKnown() const
    False when the mean cannot be computed in advance, which is not the
    same as no load.
```

DelayNode

class · Nodes.hpp · inherits public INode

Holds an entity for a duration and passes it on. No resource, no queue, no contention -- transport, cooling, walking between rooms.

```
DelayNode(std::string name, std::unique_ptr<IDistribution>
duration)
    Constructor.

DelayNode(std::string name, ExpressionPtr duration)
    Constructor.

const IExpression& durationExpression() const
    The expression giving the hold time.

IExpression& durationExpression()
    The expression giving the hold time.

void enter(NodeContext& ctx, Entity* e) override
    An entity has arrived at this block. Does the block's job and routes
    onward -- possibly not immediately.

void onScheduledEvent(NodeContext& ctx, Entity* e) override
    A previously scheduled return has come due, such as the end of a
    service or a delay.

void reset() override
    Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override
    Discards measurements collected so far and starts again from now,
    without touching what is held. This is warm-up removal at block level.

std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.

const Statistics& stats() const
    The statistics accumulator for this block.

int inTransit() const
    The in transit.
```

AssignTarget

enum class · Nodes.hpp

What an Assign writes: an entity attribute, a global variable, or the entity's type.

Values Attribute, Variable, EntityType

AssignNode

class · Nodes.hpp · inherits public INode

Sets one or more values on the entity passing through, instantly. Fields run in order, so a later field sees what an earlier one wrote.

explicit AssignNode(std::string name)

Constructor.

AssignNode& set(const std::string& attribute, std::unique_ptr<IDistribution> value)

Adds a field to this block. Fields run in the order they were added.

AssignNode& set(AssignTarget target, const std::string& name, ExpressionPtr value)

Adds a field to this block. Fields run in the order they were added.

const std::vector<Rule>& rules() const

The fields this block writes, in order.

void enter(NodeContext& ctx, Entity* e) override

An entity has arrived at this block. Does the block's job and routes onward -- possibly not immediately.

void reset() override

Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override

Discards measurements collected so far and starts again from now, without touching what is held. This is warm-up removal at block level.

std::string describe() const override

A human-readable one-line description, used in model dumps and traces.

long long count() const

How many entities have passed through.

DecideNode

class · Nodes.hpp · inherits public INode

Branches. Either by chance, from a single draw walked against cumulative probabilities, or by condition, first match wins. A block is all-chance or all-condition, never mixed.

DecideNode(std::string name, double probability)

Constructor.

DecideNode(std::string name, Condition condition)

Constructor.

DecideNode(std::string name, ExpressionPtr condition)

Constructor.

explicit DecideNode(std::string name, bool byChance)

Constructor.

DecideNode& addBranch(double probability, INode* target)

Adds a branch, in order. Order is meaningful for conditions: first match wins.

DecideNode& addBranch(Condition condition, INode* target)

Adds a branch, in order. Order is meaningful for conditions: first match wins.

DecideNode& addBranch(ExpressionPtr condition, INode* target)

Adds a branch, in order. Order is meaningful for conditions: first match wins.

void setTrueBranch(INode* n)

Sets the target of the first branch -- the two-way spelling.

INode* trueBranch() const

The true branch.

void enter(NodeContext& ctx, Entity* e) override

An entity has arrived at this block. Does the block's job and routes onward -- possibly not immediately.

void reset() override

Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override

Discards measurements collected so far and starts again from now, without touching what is held. This is warm-up removal at block level.

std::string describe() const override

A human-readable one-line description, used in model dumps and traces.

bool isByChance() const

Whether this block branches by chance rather than by condition.

double probability() const

The probability.

const std::vector<Branch>& branches() const

The branches, in evaluation order.

long long fellThrough() const

How many matched no branch.

long long tookTrue() const

How many entities took the first branch.

long long tookFalse() const

How many took any other branch or fell through.

BatchNode

class · Nodes.hpp · inherits public INode

Accumulates entities and sends one representative onward carrying them. Permanent batches consume their members; temporary ones can be split again later. Can group by matching or by distinct attribute values.

BatchNode(std::string name, std::size_t size, bool permanent = false)

Constructor.

void enter(NodeContext& ctx, Entity* e) override

An entity has arrived at this block. Does the block's job and routes onward -- possibly not immediately.

void reset() override

Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override

Discards measurements collected so far and starts again from now, without touching what is held. This is warm-up removal at block level.

std::string describe() const override

A human-readable one-line description, used in model dumps and traces.

std::size_t size() const

The size.

bool isPermanent() const

Whether permanent.

long long batchesFormed() const

The batches formed.

std::size_t waitingForBatch() const

The waiting for batch.

std::size_t maxQueueLength() const

The max queue length.

const Statistics& queueStats() const

The queue stats.

const Statistics& stats() const

The statistics accumulator for this block.

Rule rule() const

The rule.

SeparateNode

class · Nodes.hpp · inherits public INode

Splits a temporary batch back into its members, or duplicates an entity. Has two exits -- the original and the duplicate -- which is a distinction easy to lose when reading an Arena model.

void setDuplicateExit(INode* n)

Sets the duplicate exit.

INode* duplicateExit() const

The duplicate exit.

void setPercentToDuplicates(double pct)

Sets the percent to duplicates.

double percentToDuplicates() const

The percent to duplicates.

explicit SeparateNode(std::string name)

Constructor.

SeparateNode(std::string name, int copies)

Constructor.

void enter(NodeContext& ctx, Entity* e) override

An entity has arrived at this block. Does the block's job and routes onward -- possibly not immediately.

void reset() override

Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override

Discards measurements collected so far and starts again from now, without touching what is held. This is warm-up removal at block level.

std::string describe() const override

A human-readable one-line description, used in model dumps and traces.

long long processed() const

The processed.

RecordNode

class · Nodes.hpp · inherits public INode

Tallies something as entities pass: a count, an attribute value, or time in system.

explicit RecordNode(std::string name)

Constructor.

RecordNode(std::string name, std::string attribute)

Constructor.

static std::unique_ptr<RecordNode> timeInSystem(std::string name)

Builds a Record block that tallies each entity's total time in the system.

void enter(NodeContext& ctx, Entity* e) override

An entity has arrived at this block. Does the block's job and routes onward -- possibly not immediately.

void reset() override

Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override

Discards measurements collected so far and starts again from now, without touching what is held. This is warm-up removal at block level.

std::string describe() const override

A human-readable one-line description, used in model dumps and traces.

long long count() const

How many entities have passed through.

double total() const

The total.

double average() const

The average.

double minimum() const

The minimum.

double maximum() const

The maximum.

DisposeNode

class · Nodes.hpp · inherits public INode

The exit. Records the entity's departure and destroys it.

explicit DisposeNode(std::string name)

Constructor.

void enter(NodeContext& ctx, Entity* e) override

An entity has arrived at this block. Does the block's job and routes onward -- possibly not immediately.

void setNext(INode*) override

Sets the next.

void reset() override

Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override

Discards measurements collected so far and starts again from now, without touching what is held. This is warm-up removal at block level.

std::string describe() const override

A human-readable one-line description, used in model dumps and traces.

long long count() const

How many entities have passed through.

Station

class · Station.hpp · inherits public INode, public IResourceUser

The Process block: seize a resource, hold the entity for a service time, release. Also the only block that queues, balks and reneges. Implements both INode and IResourceUser.

void enter(NodeContext& ctx, Entity* e) override

An entity has arrived at this block. Does the block's job and routes onward -- possibly not immediately.

void onScheduledEvent(NodeContext& ctx, Entity* e) override

A previously scheduled return has come due, such as the end of a service or a delay.

void onRenegedTimeout(NodeContext& ctx, Entity* e) override

A patience timer has expired. Timers are never cancelled, so this checks whether the entity is still waiting and ignores the event if not.

void reset() override

Back to the t=0 condition. Configuration survives; run state does not.

void resetStatistics(SimTime now) override

Discards measurements collected so far and starts again from now, without touching what is held. This is warm-up removal at block level.

std::string describe() const override

A human-readable one-line description, used in model dumps and traces.

double loadPerVisit() const override

Mean resource-time consumed per entity passing through, divided by capacity. Used by the stability check.

bool hasWaiting() const override

Whether anything is queued here.

SimTime headOfLineSince() const override

When the longest-waiting entity here started waiting. A shared resource compares this across blocks.

void startFromQueue(NodeContext& ctx) override

Starts service for the next queued entity, if a unit is available.

void setServiceFromAttribute(const std::string& attributeName)

Takes the service time from a named attribute the entity already carries.

bool usesServiceAttribute() const

The uses service attribute.

const std::string& serviceAttributeName() const

The service attribute name.

void setRandomStream(RandomStream* rng)

Sets the random stream.

void setBalking(std::size_t queueLength, INode* balkTo)

Refuses to join a queue already this long, sending the entity elsewhere instead.

void setReneging(std::unique_ptr<IDistribution> patience, INode* renegeTo)

Gives a waiting entity a random patience, after which it gives up.

void setReneging(ExpressionPtr patience, INode* renegeTo)

Gives a waiting entity a random patience, after which it gives up.

void setUnitsNeeded(int units)

Sets the units needed.

Resource& resource()

The resource this block seizes. May be shared with other blocks.

const Resource& resource() const

The resource this block seizes. May be shared with other blocks.

EntityQueue& queue()

The waiting line at this block.

const EntityQueue& queue() const

The waiting line at this block.

Statistics& stats()

The statistics accumulator for this block.

const Statistics& stats() const

The statistics accumulator for this block.

IExpression& serviceExpression()

The expression giving the service time.

const IExpression& serviceExpression() const

The expression giving the service time.

bool loadIsKnown() const override

False when the mean cannot be computed in advance, which is not the same as no load.

```

std::size_t stillWaiting() const
    The still waiting.
long long balked() const
    The balked.
long long reneged() const
    The reneged.
int unitsHeld() const
    Units of the resource this block currently holds -- not the same as the
    resource's total busy count when it is shared.
int unitsNeeded() const
    The units needed.
SimTime drawService(NodeContext& ctx, const Entity& e)
    Evaluates the service-time expression for this entity.

```

CreateNode

class · Create.hpp · inherits public INode

An arrival source. Makes entities on its own schedule and reschedules itself. Because it is an ordinary INode, the engine has no separate arrival handler at all.

```

void enter(NodeContext& ctx, Entity* e) override
    An entity has arrived at this block. Does the block's job and routes
    onward -- possibly not immediately.
void onScheduledEvent(NodeContext& ctx, Entity* e) override
    A previously scheduled return has come due, such as the end of a
    service or a delay.
void reset() override
    Back to the t=0 condition. Configuration survives; run state does not.
void resetStatistics(SimTime now) override
    Discards measurements collected so far and starts again from now,
    without touching what is held. This is warm-up removal at block level.
std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.
const std::string& entityType() const
    The entity type.
SimTime firstAt() const
    The first at.
long long created() const
    The created.
long long maxArrivals() const
    The max arrivals.
int entitiesPerArrival() const
    The entities per arrival.
IExpression& interarrival()
    The expression giving the time until the next arrival. Evaluated with NO
    entity, because the entity does not exist yet.
const IExpression& interarrival() const
    The expression giving the time until the next arrival. Evaluated with NO
    entity, because the entity does not exist yet.
bool exhausted() const
    Whether this source has produced its maximum number of arrivals.

```

Chapter 11

The Model

What is simulated, kept separate from the machinery that simulates it.

The engine takes a Model and runs it, and knows nothing about tellers or restaurants. Model owns the blocks, the resources and the variables, and validates the flowchart before a run, catching a routing loop as an error rather than as a program that never stops.

Nested types

ArrivalAttribute is a name and a distribution, stamped on every arrival. **VisitRatios** is how often an average entity reaches each block, with an exact flag that goes false when a condition-based Decide makes the split an output of the run rather than an input. **StabilityReport** is what the offered-load check could and could not judge.

Model

class · Model.hpp

What is simulated, as opposed to the machinery that simulates it. Owns the blocks, the resources and the variables, wires them into a flowchart, and validates the result before a run.

```
Model& arrivals(std::unique_ptr<IDistribution> d)
    The single-source shorthand: creates a source called Arrivals.

Model& arrivals(const std::string& interarrivalText)
    The single-source shorthand: creates a source called Arrivals.

Model& allowOverload(bool on = true)
    Permits a model whose queues grow without bound. Correct for a
    terminating run, meaningless for a steady-state study, and the report
    says so.

bool overloadAllowed() const
    Whether overload has been permitted.

void setInterarrival(std::unique_ptr<IDistribution> d)
    Sets the interarrival.

Model& variable(const std::string& name, double initialValue
= 0.0)
    Declares a global variable. Checks it does not collide with an attribute
    name.

VariableStore& variables()
    The variable store.

const VariableStore& variables() const
    The variable store.

Model& attribute(const std::string& name,
std::unique_ptr<IDistribution> d)
    Declares an attribute stamped on every arrival, drawn from a
    distribution.

void assignOnArrival(const std::string& n,
std::unique_ptr<IDistribution> d)
    Alias for attribute(): stamps a drawn value on every arriving entity.

const std::vector<ArrivalAttribute>& arrivalAttributes()
const
    The attributes stamped on every arrival.

Model& resource(const std::string& name, int capacity)
    Declares a shared resource that several blocks may seize.

std::size_t resourceCount() const
    How many shared resources the model declares. Name lookup cannot
    enumerate, and a snapshot has to.

const Resource& resourceAt(std::size_t i) const
    One declared resource, by position.

Resource* resourceNamed(const std::string& name)
    Looks a resource up by name.

const Resource* resourceNamed(const std::string& name) const
    Looks a resource up by name.

Model& decideNWayByChance(const std::string& name)
    Starts an N-way Decide branching by chance.

Model& decideNWayByCondition(const std::string& name)
    Starts an N-way Decide branching by condition.
```

```
Model& branch(const std::string& decideName, double
probability, const std::string& to)
    Adds a branch to an N-way Decide, in order.

Model& delay(const std::string& name,
std::unique_ptr<IDistribution> duration)
    Adds a Delay block.

Model& delay(const std::string& name, const std::string&
durationText)
    Adds a Delay block.

Model& assign(const std::string& name)
    Adds or extends an Assign block. Calling it again with the same name
    adds another field.

Model& assignEntityType(const std::string& block, const
std::string& typeText)
    Restamps the entity's type from an expression.

Model& decideByChance(const std::string& name, double
probabilityTrue)
    Adds a two-way Decide taking the true branch with a fixed probability.

Model& decideByCondition(const std::string& name,
DecideNode::Condition condition)
    Adds a two-way Decide on a predicate or expression.

Model& decideByCondition(const std::string& name,
ExpressionPtr condition)
    Adds a two-way Decide on a predicate or expression.

Model& decideWhen(const std::string& name, const
std::string& conditionText)
    Adds a two-way Decide whose condition is written as text.

Model& batch(const std::string& name, std::size_t size, bool
permanent = false)
    Accumulates entities into groups of a given size.

Model& separate(const std::string& name)
    Splits a temporary batch back into its members.

Model& duplicate(const std::string& name, int copies)
    Copies an entity a given number of times.

Model& record(const std::string& name)
    Counts entities passing a point.

Model& recordAttribute(const std::string& name, const
std::string& attributeName)
    Tallies an attribute's value as entities pass.

Model& recordTimeInSystem(const std::string& name)
    Tallies time in system as entities pass.

Model& dispose(const std::string& name)
    Adds a named exit.

Model& route(const std::string& from, const std::string& to)
    Connects one block's default exit to another block.

Model& routeTrue(const std::string& decideName, const
std::string& to)
    Connects a Decide's true branch.

Model& routeDuplicate(const std::string& separateName, const
std::string& to)
    Connects a Separate's duplicate exit. Its original exit is plain route().

Model& entryAt(const std::string& name)
    Names the block arrivals enter at.

void connect(const std::string& f, const std::string& t)
    Alias for route().

void setEntry(const std::string& n)
    Alias for entryAt().

INode* node(const std::string& name)
    Looks a block up by name.

const INode* node(const std::string& name) const
    Looks a block up by name.

INode* entry() const
    The block arrivals enter at.

template <typename T> T& nodeAs(const std::string& name)
```

Looks a block up by name and type, throwing if either is wrong rather than returning a null the caller will dereference later.

Station* station(const std::string& name)

Looks a Process block up by name.

const Station* station(const std::string& name) const

Looks a Process block up by name.

std::size_t stationCount() const

How many Process blocks the model has.

Station& stationAt(std::size_t i)

The i-th Process block. Process blocks are the only ones a utilisation table means anything for.

const Station& stationAt(std::size_t i) const

The i-th Process block. Process blocks are the only ones a utilisation table means anything for.

std::size_t sourceCount() const

How many arrival sources the model has.

CreateNode& sourceAt(std::size_t i)

The i-th arrival source.

const CreateNode& sourceAt(std::size_t i) const

The i-th arrival source.

std::size_t nodeCount() const

How many blocks the model has in total.

Inode& nodeAt(std::size_t i)

The i-th block, of any kind.

const Inode& nodeAt(std::size_t i) const

The i-th block, of any kind.

StabilityReport stability() const

What the offered-load check could and could not verify.

bool arrivalRateIsKnown() const

False when any source's interarrival mean cannot be computed in advance, which makes every station's load unknowable too.

std::vector<Diagnostic> checkExpressions() const

Validates every expression in the model against the declared names, returning diagnostics rather than throwing.

std::vector<Diagnostic> checkStructure() const

The check structure.

VisitRatios visitRatios() const

How many times an average entity passes through each block.

double offeredLoad(const Station& s) const

The offered load at one Process, summed over every arrival stream and weighted by visits.

void wireSources()

Connects the shorthand source to the entry block, so the order a model is described in does not matter.

void reset()

Back to the t=0 condition. Configuration survives; run state does not.

void validate() const

Checks the whole model and throws on the first problem. Catches routing loops before they become a hang.

std::string describe() const

The whole model as text, block by block.

Chapter 12

Running a Simulation

The engine, the stopping rules, and the trace that makes a run checkable by hand.

SimulationSystem owns the clock, the event list, the entities, the random streams and the model. It also implements IModelState, which is how an expression reads the running system without the expression layer depending on the model.

SimulationSystem

class · SimulationSystem.hpp · inherits public IModelState

The engine. Owns the clock, the future event list, the entities, the random streams and the model, and runs the loop that drives them. Also implements IModelState so expressions can read the running system.

```
explicit SimulationSystem(unsigned seed = 12345u)
    Constructor.

double queueLength(const std::string& blockName) const
    override
    How many entities wait at a named block. Part of IModelState, so
    expressions can read it. Throws on an unknown name rather than
    reading as an empty queue.

double resourceBusy(const std::string& name) const override
    Units of a named resource currently seized. A Process with a private
    resource is addressable by the block's name.

double resourceCapacity(const std::string& name) const
    override
    A named resource's capacity.

double numberInSystem() const override
    How many entities are anywhere in the system.

SimTime now() const override
    The current simulation time.

double variableAverage(const std::string& name) const
    The time-weighted average of a global variable.

void reportStability(std::ostream& os) const
    Prints the blocks the offered-load check could not verify. Prints nothing
    when everything was checked.

Model& model()
    The model being simulated.

const Model& model() const
    The model being simulated.

void setTermination(std::unique_ptr<ITerminationRule> rule)
    Sets an arbitrary stopping rule.

void setWarmUp(SimTime t)
    Discards statistics collected before this time.

void setObservationInterval(SimTime dt)
    Samples number-in-system on a fixed grid, for Welch plots.

SimulationSystem& useSeparateStreams(bool on = true)
    Gives each named role its own random stream, which is what makes
    two model variants comparable.

SimulationSystem& useAntithetic(bool on = true)
    Turns on antithetic variates.

bool isAntithetic() const
    Whether antithetic.

const std::vector<double>& observations() const
    The observations.

SimTime measuredTime() const
    The measured time.

SimTime warmUpEnd() const
    The warm up end.

bool enableTrace(const std::string& path, TraceLevel level,
    bool markdown = true)
    Starts writing an event log to a file.

const Clock& clock() const
    The simulation clock.

const Statistics& statistics() const
```

The statistics.

```
const SystemState& state() const
    The state.

const FutureEventList& fel() const
    The fel.

const RandomStream& randomStream() const
    The random stream.

const ITerminationRule* termination() const
    The stopping rule currently set, so a caller can ask it how far through
    the run is.

std::size_t liveEntityCount() const
    The live entity count.

Entity* createEntity()
    Makes an entity and registers it in the entity table. Called through
    NodeContext, never directly by a block.

void initialise()
    Validates the model, resets everything holding run state, and
    schedules the first arrival. Must be called before run().

void run()
    The event loop: pop the earliest event, close the integrals for the
    interval that just ended, move the clock, then dispatch. That order is
    not negotiable.

bool canStep() const
    Whether another event can be processed: one is pending, no stopping
    rule is met, and no EndSimulation event has fired. Deliberately does
    not test whether initialise() has been called -- that is a precondition the
    callers assert, and folding it in would turn a forgotten initialise() into a
    run that silently does nothing.

bool stepOnce()
    Processes the imminent event and reports whether it did. run() is a
    loop over this and nothing else -- the same loop, with the caller holding
    the handle.

void report(std::ostream& os) const
    Prints the run's results.

void report() const
    Prints the run's results.

void reportArenaStyle(std::ostream& os) const
    Prints the same numbers in Arena's report layout.

void reportArenaStyle() const
    Prints the same numbers in Arena's report layout.

SimulationSystem& execute()
    initialise() and run() in one call, for the common case.

RunResults results() const
    The run's numbers, derived once.

const std::map<std::string, TypeStats>& byType() const
    Per-entity-type counts and times.

SimulationSystem& stopWhen(std::unique_ptr<ITerminationRule>
    rule)
    Sets an arbitrary stopping rule, returning *this so it chains.

SimulationSystem& stopAt(SimTime t)
    Stops the run at a given time.

SimulationSystem& stopAfter(int entities)
    Stops after a given number of entities have left.

SimulationSystem& warmUpFor(SimTime t)
    Discards statistics collected before this time, returning *this so it
    chains.
```

StationResults

struct · SimulationSystem.hpp

One block's numbers after a run: served, utilisation, average wait, queue length.

RunResults

struct · SimulationSystem.hpp

The whole run's numbers, derived once so that printing is only a view of them.

```
const StationResults& station(const std::string& name) const
    One block's results, by name.
```

ITerminationRule

class · TerminationRule.hpp

The interface a stopping condition implements. Asked after every event whether the run should end.

```
virtual bool isMet(const SimulationSystem& sim) const = 0
    Whether this stopping condition now holds.
virtual std::string describe() const = 0
    A human-readable one-line description, used in model dumps and
    traces.
virtual std::optional<double> progress(const
SimulationSystem&) const
    How far through this rule the run is, or NOTHING when it cannot tell.
    Nothing does not mean zero: a drained-system rule has no knowable
    fraction, and a progress bar that reads 0% throughout and then jumps
    to 100% is a lie the caller cannot detect.
```

TimeLimit

class · TerminationRule.hpp · inherits public ITerminationRule

Stop when the clock reaches a given time.

```
explicit TimeLimit(SimTime maxTime)
    Constructor.
bool isMet(const SimulationSystem& sim) const override
    Whether this stopping condition now holds.
std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.
std::optional<double> progress(const SimulationSystem& sim)
const override
    The clock over the limit, clamped to 1. A time limit always knows how
    far through it is.
SimTime maxTime() const
    The max time.
```

EntityLimit

class · TerminationRule.hpp · inherits public ITerminationRule

Stop after a given number of entities have left the system.

```
explicit EntityLimit(int maxEntities)
    Constructor.
bool isMet(const SimulationSystem& sim) const override
    Whether this stopping condition now holds.
std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.
std::optional<double> progress(const SimulationSystem& sim)
const override
    Entities served over the limit, clamped to 1.
```

DrainedRule

class · TerminationRule.hpp · inherits public ITerminationRule

Stop when nothing is left in the system. Fires at the first moment the system is empty, which may be a transient gap rather than the end of the work.

```
bool isMet(const SimulationSystem& sim) const override
    Whether this stopping condition now holds.
std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.
```

AnyOf

class · TerminationRule.hpp · inherits public ITerminationRule

Stops when any composed rule says stop.

```
AnyOf& add(std::unique_ptr<ITerminationRule> rule)
    Adds a rule; the composite stops when any of them does.
bool isMet(const SimulationSystem& sim) const override
    Whether this stopping condition now holds.
std::string describe() const override
    A human-readable one-line description, used in model dumps and
    traces.
std::optional<double> progress(const SimulationSystem& sim)
const override
    The LARGEST fraction any child knows, because the run ends when
    the FIRST rule is met and the most advanced child is the honest
    estimate. Nothing when no child can tell -- not zero.
bool empty() const
    Whether any rules have been added. An AnyOf with none never stops
    the run.
```

TraceLevel

enum class · Trace.hpp

How much detail the trace records, from off to every event.

Values Off, Events, Detailed

Trace

class · Trace.hpp

Writes an event-by-event log, optionally as a markdown table. Traces diff, which is what makes a behaviour change show up as a diff rather than as a slightly-off average.

```
~Trace()
    Destructor.
bool open(const std::string& path, TraceLevel level, bool
markdown = true)
    Starts writing a trace to a file.
void close()
    Closes the trace file. Called by the destructor, so this is only for closing
    early.
bool isOn() const
    Whether tracing is enabled. Callers check this before building a
    message.
TraceLevel level() const
    The level.
long long lineCount() const
    How many lines have been written, so a test can assert a trace was
    produced.
void note(const std::string& text)
    Writes a free-text line into the trace, outside the event table.
```

Chapter 13

Experiments

Why one run is one sample, and what to do about it.

A single run is one observation of a random variable. Quoting it to four decimals implies a precision that does not exist. Experiment runs the model many times with independent seeds and reports an interval.

Nested types

Estimate is a point estimate with its confidence interval. **Comparison** is two configurations and the interval on their difference, which is what actually answers whether a change did anything.

ReplicationResult

struct · Experiment.hpp

One replication's summary figures, so a set of runs can be treated as a sample.

Summary

class · Experiment.hpp

The statistics of a sample of replications: mean, standard deviation, standard error and a 95% half-width from Student's t.

```
static double mean(const std::vector<double>& xs)
    The theoretical mean, used by the stability check before the run.

static double stdDev(const std::vector<double>& xs)
    Sample standard deviation, with the n-1 denominator.

static double standardError(const std::vector<double>& xs)
    Standard deviation divided by the square root of the sample size.

static double halfWidth95(const std::vector<double>& xs)
    Half the width of a 95% confidence interval, from Student's t.

static double tCritical95(int degreesOfFreedom)
    The two-sided 95% critical value of Student's t.
```

Experiment

class · Experiment.hpp

Runs a model many times with independent seeds and reports an interval rather than a number. Also implements Welch's method for finding the warm-up period.

```
Experiment(std::string name, Builder build)
    Constructor.

Experiment& replications(int n)
    How many independent runs to make.

Experiment& baseSeed(unsigned s)
    The seed the per-replication seeds are derived from.

Experiment& warmUp(SimTime t)
    The warm-up period applied to every replication.

Experiment& observeEvery(SimTime dt)
    The observation grid used for Welch's method.

Experiment& separateStreams(bool on = true)
    Turns on per-role random streams for every replication.

Experiment& antitheticPairs(bool on = true)
    Pairs each replication with its antithetic twin.

void run()
    Runs every replication and collects the results.

const std::vector<ReplicationResult>& results() const
    The results.

std::vector<double> column(double ReplicationResult::*
field) const
    Pulls one field out of every replication result as a plain vector, so any of
    them can be summarised the same way.

std::vector<double> waits() const
```

The waits.

```
std::vector<double> timesInSystem() const
    The times in system.

std::vector<double> queueLengths() const
    The queue lengths.

std::vector<double> utilisations() const
    The utilisations.

static Estimate estimate(const std::vector<double>& xs)
    A point estimate with its interval, from a sample.

std::vector<double> welchAverages(int window) const
    The Welch moving average across replications, for finding the
    transient.

SimTime suggestWarmUp(int window = 0, double maxFraction =
0.5) const
    A warm-up length suggested by MSER. A starting point, not an
    answer.

bool writeWelchSeries(const std::string& path, int window)
const
    Writes the Welch series to a CSV so it can be plotted.

void report() const
    Prints each quantity as a mean with a 95% confidence interval.
```


Chapter 14

Call Flows


What calls what, in order, when a model is built and run.

These traces follow examples/16_expressions.cpp, which exercises every part of the engine: text expressions, a condition reading a queue, a global variable, and a Decide by chance.

1 - building and starting




2 - initialise()




Order matters here: the model is validated BEFORE run state is reset, so a broken model fails without having touched anything.

3 - the run loop



4 - an arrival



5 - service, and a freed unit




The freed unit is offered through the resource rather than handed back to this block's own queue, because with a shared resource somebody at another block may have been waiting longer.

6 - evaluating an expression




The expression layer declares *IModelState* and *SimulationSystem* implements it, so the dependency points downward and the expression layer never includes *Model.hpp*.

7 - a Decide by condition



A by-chance Decide takes ONE draw and walks it against the cumulative probabilities. Drawing once per branch would burn several random numbers and would not give the branch probabilities you asked for.

8 - des check model.des



Blocks are created before their exits are wired for the same reason *wireSources()* exists: the order a model is described in must not matter, and *route()* refuses a target that does not exist yet. Every pass runs, so one command reports every bad cell rather than the first.

Chapter 15

Free Functions

The factories and helpers that are not members of anything.

Distribution factories, from Build.hpp

Thin wrappers so a model reads as a description rather than as memory management.

Function	Builds
exponential(mean)	Exponential. Takes a MEAN, not a rate.
constant(v)	Constant. Consumes nothing from the stream.
uniform(a, b)	Uniform on a closed interval.
triangular(a, mode, b)	Triangular.
normal(mean, sd, truncate)	Normal, truncated at zero by default.
lognormal(logMean, logSd)	Lognormal from log-space parameters.
lognormalFrom(mean, sd)	Lognormal from observed mean and sd.
weibull(scale, shape)	Weibull.
erlang(totalMean, phases)	Erlang with the mean you want.
discrete(values, probs)	Discrete, individual probabilities.
empirical(observations)	Empirical, sampled from data.
poisson(mean)	Poisson counts.
fixedTimes(values, repeat)	Deterministic. The basis of hand checks.

Termination rules, from Build.hpp

Function	Stops when
timeLimit(t)	the clock reaches t.
entityLimit(n)	n entities have left.
whenDrained()	the system is empty, which may be a transient gap.
anyOf(a, b, ...)	any composed rule fires.

The platform boundary, from Terminal.hpp

The only functions that differ by operating system. Everything above them is a value a test can inspect; these are the part that cannot be.

Function	Does
openTerminal(whyNot)	The console in raw mode -- or null with the reason, when input or output is redirected or the console cannot draw.
defaultModelPath()	Where a model goes when the program starts with no file: untitled.des in a DES Models folder inside the real Documents folder, asked of Windows so that one redirected into OneDrive is found.
launchedOnOwnConsole()	Whether this program is alone on its console -- double-clicked -- so a message printed on the way out needs the window held open to be read.

Reading a document

Function	Does
referenceCandidates(doc, type)	Every name a Reference column may hold. The pick list and the reference pass are this one function, so a list cannot offer a name that is then rejected.
lineOf(doc, diagnostic)	Which line of the file a diagnostic is about, or 0 when it cannot say. A diagnostic names a cell; an editor needs a line.
runNames(doc)	The Name of each [Run] record, with a stand-in for one that has none.
readRunSetup(doc, out, which)	One [Run] record by position; past the end it reads as the defaults rather than as an error.
flowOf(doc)	The flowchart as the Flow view shows it, read from the cells so it still works on a model that does not compile.
templateFor(schema)	The lines a module inserts: its header, then every field, blank.
blockTypeAt / keyOfLine	Which record a line of text is inside, and the key of a key = value line.
starterModelText()	A working single-server model, as text, with its comments.

The expression layer

Function	Does
tokenise(text)	Text to tokens with spans. Never throws.
parseExpression(text)	Tokens to a tree plus diagnostics. Never throws.
expr(text)	The same, but throws. For C++ callers.
isBuiltinFunction(name)	Whether a name is in the call table.
isNumber / isText	Which half of a Value is present.
asNumber / asText	Reads a Value, throwing rather than coercing.
truthy(v)	Non-zero is true; text throws.
formatValue(v)	A Value as text, whole numbers without a point.
hasErrors(diags)	Whether any diagnostic is an error.
formatDiagnostics(diags)	Diagnostics as text, one per line.
describe(TokenKind)	Names a token kind, for messages.
spelling(op)	An operator's symbol.

Grammar functions

Usable inside any expression field. Distributions: EXPO, CONS, UNIF, TRIA, NORM, LOGN, WEIB, ERLA, POIS, DISC. Model state: NQ(block), NR(name), MR(name), WIP(), and the constant TNOW. Maths: MIN, MAX, ABS, ROUND, TRUNC, SQRT, LN, EXP, MOD.

Three traps. EXPO is the exponential distribution while EXP is e to the x, which is Arena's collision kept deliberately. DISC takes CUMULATIVE probabilities as Arena writes them, while the engine's own discrete() takes individual ones. LOGN takes the mean and standard deviation of the variable, not of its logarithm.